



NOTES

1. PLUG & BULKHEAD TO BE INSTALLED ON DOWNSTREAM (OUTLET) ON MAINTENANCE HOLE.
2. PLUG SHALL BE CHERNE "INSIDE-OF-PIPE GRIPPER" OR APPROVED EQUIVALENT
3. PLUG TO BE TIED OFF TO MAINTENANCE HOLE LADDER RUNG.
4. BRICK SHALL BE COMMON SEWER RED BRICK AS PER ASTM C-32 OR APPROVED EQUIVALENT.
5. CEMENT MORTAR SHALL BE HYDRAULIC CEMENT COMPRISED OF 1 PART PORTLAND CEMENT, 2 PARTS MORTAR SAND BY VOLUME. CEMENT AND SAND SHALL COMPLY WITH OPSS.



SANITARY PLUG AND BULKHEAD DETAIL

DRAWN: A&A

APR'D:

SCALE: N.T.S.

DATE: SEPT 2025

NO.

REVISIONS

APR'D

DATE

METRIC
ALL DIMENSIONS IN mm
UNLESS OTHERWISE NOTED

TOISD
612