


FLANGE END METER

40 mm - UP



PLAN VIEW

NOTES

1. WATER METER TO BE A MINIMUM 600mm FROM ANY WALL OR IMMOVABLE OBJECT.
2. DOMESTIC WATER SERVICE AND BY-PASS TO BE EQUAL IN SIZE.
3. BACKFLOW PREVENTER REQUIRED BEYOND THE BY-PASS. BACKFLOW PREVENTER TO BE DETERMINED BY A QUALIFIED PERSON IN ACCORDANCE WITH THE INNISFIL BACKFLOW PREVENTION BY-LAW, AND IN ACCORDANCE WITH CSA B64 SERIES.
4. METERS 40 mm AND LARGER TO HAVE REMOVABLE SUPPORTS TO INNSERVICES SATISFACTION. PIPE SUPPORTS TO CONFORM TO PART 7 OF OBC.
5. EXPANSION TANK REQUIRED BEYOND THE BACKFLOW PREVENTER AS PER PART 7 OF THE OBC.
6. PRESSURE REDUCING VALVES, IF REQUIRED, MUST BE LOCATED BEYOND THE BY-PASS AND BACKFLOW PREVENTER.



TYPICAL WATER METER INSTALLATION (40mm AND UP)

DRAWN:

SCALE: N.T.S.

APRD:

DATE: JUNE 2011

3.	REVISED NOTES	TOI	SEPT 2025
2.	TO REFLECT TOWN STANDARDS	TOI	APRIL 2018
1.	REVISED TOWN LOGO	TOI	APRIL 2015
NO.	REVISIONS	APRD	DATE

METRIC
ALL DIMENSIONS IN mm
UNLESS OTHERWISE NOTED

**TOISD
708**